

UNCLASSIFIED

AD NUMBER

ADB021491

LIMITATION CHANGES

TO:

Approved for public release; distribution is unlimited.

FROM:

Distribution authorized to U.S. Gov't. agencies only; Test and Evaluation; 28 JUL 1977. Other requests shall be referred to Air Force Packaging Evaluation Agency, Wright-Patterson AFB, OH 45433.

AUTHORITY

usafald ltr 27 jan 1982

THIS PAGE IS UNCLASSIFIED

THIS REPORT HAS BEEN DELIMITED
AND CLEARED FOR PUBLIC RELEASE
UNDER E.O. DIRECTIVE 5200.20 AND
NO RESTRICTIONS ARE IMPOSED UPON
ITS USE AND DISCLOSURE.

DISTRIBUTION STATEMENT A
APPROVED FOR PUBLIC RELEASE
DISTRIBUTION UNLIMITED.

28 July 1977

DISTRIBUTION LIMITED to U.S. Government agencies only; ~~report involves evaluation of commercial products.~~ Other requests for this document must be referred to AFALD/PTP, Wright-Patterson AFB OH 45433

PTPD REPORT NO. 77-22

AFPEA PROJECT NO. 77-P7-23

ADB021491

RICHARD T. GIBBONS
Mechanical Engineer

AUTOVON 787-3120
Commercial (513) 257-3120



TESTING AND ANALYSIS OF HOUSEHOLD GOODS CONTAINERS

AD No. _____
DDC FILE COPY

AFALD/PTPD
Air Force Packaging Evaluation Agency
Wright-Patterson AFB OH 45433

July 1977

NOTICE

When government drawings, specifications, or other data are used for any purpose other than in connection with a definitely related government procurement operation, the United States Government thereby incurs no responsibility whatsoever; and the fact that the government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data, is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use, or sell any patented invention that may in any way be related thereto. This report is not to be used in whole or in part for advertising or sales purposes.

ABSTRACT

As part of the Air Force Packaging Evaluation Agency (AFPEA) mission, test and evaluation services are available to all agencies in the DOD. These services are used to evaluate a single container design or to compare and contrast various designs and products from a variety of sources. Through this engineering effort, AFPEA is able to help make sure the best and most economical containers are used in the transportation system.

Recently, the Design Division of AFALD/PTP conducted testing and evaluation of six household goods containers. While none of the containers passed the testing criteria established, there was ample opportunity to observe the effect of variations in construction. It is very probable that with more emphasis on the container seal design, one or more of the tested containers can successfully pass all tests required.

ACCESSION FOR	
NTIS	White Section <input checked="" type="checkbox"/>
DDC	Buff Section <input checked="" type="checkbox"/>
UNANNOUNCED	<input type="checkbox"/>
JUSTIFICATION	
BY	
DISTRIBUTION/AVAILABILITY CODES	
Dist.	AVAIL. and/or SPECIAL
B	

PREPARED BY:

Richard T. Gibbons
RICHARD T. GIBBONS
Mechanical Engineer
Design Division

REVIEWED BY:

Ralph Zynda
RALPH ZYND
CHIEF, DESIGN DIVISION
Air Force Packaging
Evaluation Agency

PUBLICATION DATE:

28 July 1977

APPROVED BY:

Jack E. Thompson
JACK E. THOMPSON
Director, Air Force Packaging
Evaluation Agency

TABLE OF CONTENTS

ABSTRACT.	1
TABLE OF CONTENTS	111
INTRODUCTION.	1
PHASE I	3
Procedures and Results	5 - 9
Figures 1 - 8.	10 - 13
PHASE II.	15
Procedures and Results	17 - 21
Figures 9 - 16	22 - 25
PHASE III	27
Procedures and Results	29 - 33
Figures 17 - 24.	34 - 37
PHASE IV.	39
Procedures and Results	41 - 45
Figures 25 - 28.	46 - 47
PHASE V	49
Procedures and Results	51 - 55
Figure 29.	56
DISCUSSION.	57
RECOMMENDATIONS	57
DISTRIBUTION LIST	59 - 61
DD FORM 1473.	63 - 64

INTRODUCTION

The Air Force Packaging Evaluation Agency (AFPEA) has completed testing of five household goods containers, one each from five separate manufacturers. Initial testing was conducted at the request of GSA as part of a container evaluation program. An additional container was submitted to the AFPEA testing facilities as part of the 'compare and contrast' function of the evaluation.

Following is a list of container manufacturers in the order of container testing:

1. ARBI CONTAINER COMPANY, INC.
2. PAK-WELL INC.
3. HUGHES BOX AND CONTAINER COMPANY
4. ROWLEY & ASSOCIATES
5. WR-ALC (SPECIAL DESIGN EFFORT)
6. BLAKELY (NOT TESTED)

AFPEA acted as the independent and unbiased agency for all testing. MIL-STD-1489A, "Performance Testing of Commercially Owned Household Goods Containers," was strictly followed in both preparation and testing of all containers. The following sections contain each test report as required by MIL-STD-1489A, along with representative photographs.

PHASE I

PROCEDURE

The following test report requirements are provided to comply with Appendix A of MIL-STD-1489A, "Performance Testing of Commercially Owned Household Goods Containers."

SECTION 1 - IDENTIFICATION INFORMATION

1. Test Report Date of Issuance -- 27 April 1977
2. Container Manufacturer -- ARBI Container Company, Inc.
P.O. Box 3588
Jackson MS 39207
3. Testing Sponsor -- J. Burton, Federal Supply Service
4. Carrier Representative -- N/A
5. Test Laboratory -- Air Force Packaging Evaluation Agency
HQ AFALD/PTP
Wright-Patterson AFB OH 45433
6. Government Representatives -- R. T. Gibbons, F. R. Yeager
P. Quijas, J. H. Schenck
7. Container Built in Accordance With -- PPP-B-00580 (Navy)
Amendment 1. Deviations only as authorized in Government contract.

SECTION 2 - CONTAINER CONFIGURATION CHARACTERISTICS

1. Exterior Dimensions -- 96 1/2 x 42.5 x 84
2. Exterior Volume -- 199.4
3. Interior Dimensions -- 93.5 x 39.75 x 78.5
4. Interior Volume -- 168.8 cu ft
5. Ratio Interior to Exterior Volume -- 0.85:1
6. Tare Weight -- 415
7. Tare Density -- 2.08 pcf
8. Cube Utilization -- (8 x 8 x 20 VAN) - Actual - 4 containers
with 582 cu ft unused volume

SECTION 3

TEST RESULTS (A)

1. Test Method 500, Drop Test
2. Conducted on: 20 April 1977
3. Method 500, Drop Test, was conducted in strict compliance with MIL-STD-1489A, with no deviations.
4. No test measurements required.
5. Post inspection revealed the following:
 - a. At conclusion of edge drops -
 - (1) A small separation developed between the header and the skid.
 - (2) Splits developed in the side horizontal cleats where the clip hardware screws entered.
 - (3) Separation between the side and end seams became evident.
 - b. At conclusion of corner drops -
 - (1) All cleats showed some evidence of splitting at the clip hardware screw entrance points similar to that described in 5.a.(2) above.
 - (2) Small crack developed in one side plywood panel.
6. The container's performance was satisfactory when evaluated against the criteria established in paragraph 7, Method 500 of MIL-STD-1489A.

TEST RESULTS (B)

1. Test Method 501, Stacking Test
2. Conducted on: 20 April 1977
3. Method 501, Stacking Test, was conducted in strict compliance with MIL-STD-1489A with no deviations. The test apparatus used to provide a constant test load was a Testing Machines Inc. (TMI), high capacity compression tester, model no. 17-24-2 with graphic and digital readout of load and deflection.

4. Test measurements. The magnitude of the superimposed load was kept constant for over one hour at 7120 lbs. The testing machine was programmed to prevent load drop-off due to the relaxation of the material. Maximum bulging on the container occurred on side #3. This displacement was 1.32" from the no-load conditions.
5. Post-test inspection findings showed no damage to the container.
6. The container's performance was satisfactory when evaluated against the criteria established in paragraph 7, MIL-STD-1489A, Method 501.

TEST RESULTS (C)

1. Test Method 502, Racking Test
2. Conducted on: 20 April 1977
3. Method 502, Racking Test, was conducted in strict compliance with MIL-STD-1489A with no deviations.
4. Test measurements were as follows:
 - a. A 360 lb compressive force was necessary to lift the container's unrestricted sides just clear of the supporting surface.
 - b. The maximum change in length of a diagonal was 0.25" on side #2 in the direction away from the restricted side.
5. Post-test inspection findings show no damage to the container.
6. The container's performance was satisfactory when evaluated against the criteria established in paragraph 7, MIL-STD-1489A, Method 502.

TEST RESULTS (D)

1. Test Method 503, Pendulum Impact Test
2. Conducted on: 20 April 1977
3. Method 503, Pendulum Impact Test, was conducted in strict compliance with MIL-STD-1489A with no deviations.

4. No test measurements required.
5. Post-test inspection findings showed the following:
 - a. All clip hardware screw entry points showed cracks developing or spreading.
 - b. All seams continued to open slightly. This was mostly visible on the end/side seams.
 - c. On end 3-2 a large split developed. This was a continuation of a crack developed in the drop test sequence.
 - d. Several staple heads had popped up on the inside of the container. Maximum displacement of the staple head was approximately 0.125".
6. The container's performance was marginal when evaluated against the criteria established in paragraph 7, MIL-STD-1489A, Method 503. It is extremely doubtful that this container would withstand the multi-trip environment for which it was designed.

TEST RESULTS (E)


1. Test Method 504, Watertightness Test
2. Conducted on 20 April 1977
3. Method 504, Watertightness Test, was conducted in strict compliance with MIL-STD-1489A with no deviations.
4. No test measurements required.
5. Post-test inspection findings revealed a small amount of water on the interior sides and ends. The side/end seams showed a slight trace of water. The major area of water entrance was at the container interior base. There was a considerable amount of standing water covering approximately 55 percent of the floor.
6. The container's performance was unsatisfactory when evaluated against the criteria established in paragraph 7, MIL-STD-1489A, Method 504.

TEST RESULTS (F)

1. Test Method 505, Pendulum Puncture Test
2. Conducted on 20 April 1977
3. Method 505, Pendulum Puncture Test, was conducted in strict compliance with MIL-STD-1489A with no deviations.
4. No test measurements required.
5. Post-test inspection findings showed the impact surfaces pulled away from the lower horizontal cleats during each of the four impacts. This was due in all probability to the non-clinching of the cement-coated staples used to join the plywood panels to the cleats. The staple was in accordance with PPP-B-00580 (Navy) "Box, Wood, Household Goods," Amendment 1, paragraph 3.3.3.2.
6. The container's performance was unsatisfactory when evaluated against the criteria established in paragraph 7, MIL-STD-1489A, Method 505.

SECTION 4 - VERIFICATION

The Air Force Packaging Evaluation Agency has no direct financial interest in either the design or manufacture of the container. The test equipment, test procedures, test conditions, and sequences of testing employed conformed to all applicable provisions of the document. The test report accurately depicts the test findings.



JACK E. THOMPSON
Director
Air Force Packaging
Evaluation Agency



FIGURE 1. THE ARBI CONTAINER COMPANY
CONTAINER PRIOR TO END PENDULUM PUNCTURE TEST



FIGURE 2. CLEATED CORNER SEALED WITH CAULKING



FIGURE 3. END DAMAGED DURING DROP TEST SEQUENCE




FIGURE 4. ADDITIONAL CORNER DAMAGE FROM IMPACT




FIGURE 5. EQUIPMENT SET-UP PRIOR TO END PENDULUM PUNCTURE TEST




FIGURE 6. DAMAGE RESULTING FROM END PENDULUM PUNCTURE TEST




FIGURE 7. DAMAGE RESULTING FROM SIDE PENDULUM PUNCTURE TEST




FIGURE 8. TOP VIEW OF PLYWOOD/CLEAT SEPARATION

PHASE II

PROCEDURE

The following test report requirements are provided to comply with Appendix A of MIL-STD-1489A, "Performance Testing of Commercially Owned Household Goods Containers."

SECTION 1 - IDENTIFICATION INFORMATION

1. Test Report Date of Issuance - 19 May 1977
2. Container Manufacturer - PAK WELL INC.
673 Morgan Avenue
Brooklyn NY 11222
3. Testing Sponsor - J. Burton, Federal Supply Service
4. Carrier Representative - N/A
5. Test Laboratory - Air Force Packaging Evaluation Agency
HQ AFALD/PTP
Wright-Patterson AFB OH 45433
6. Government Representatives - Richard T. Gibbons
Frank R. Yeager
7. Container Built in Accordance With - PPP-B-00580 (Navy)
Amendment 1. Deviations only as authorized in Government contract.

SECTION 2 - CONTAINER CONFIGURATION CHARACTERISTICS

1. Exterior Dimensions - 96 1/2 x 42.5 x 84
2. Exterior Volume - 199.4
3. Interior Dimensions - 93.5 x 39.75 x 78.5
4. Interior Volume - 168.8 cu ft
5. Ratio Interior to Exterior Volume - 0.85:1
6. Tare Weight - 415 lbs
7. Tare Density - 2.08 pcf
8. Cube Utilization (8 x 8 x 20 VAN) - Actual - 4 containers
with 582 cu ft unused volume

SECTION 3 - TEST RESULTS (A)

1. Test Method 500, Drop Test
2. Conducted on 12 May 1977
3. Method 500, Drop Test, was conducted in strict compliance with MIL-STD-1489A, with no deviations.
4. No test measurements required.
5. Post inspection revealed the following:
 - a. At conclusion of edge drops there was no damage apparent.
 - b. At the conclusion of the corner drops there was a minimal amount of damage in the impact areas.
6. The container's performance was satisfactory when evaluated against the criteria established in MIL-STD-1489A, Method 500, paragraph 7.

TEST RESULTS (B)

1. Test Method 501, Stacking Test
2. Conducted on: 12 May 1977
3. Method 501, Stacking Test, was conducted in strict compliance with MIL-STD-1489A with no deviations. The test apparatus used to supply a constant test load was a Testing Machines Inc. (TMI), high capacity compression tester, model no. 17-24-2 with graphic and digital readout of load and deflection.
4. Test measurements. The magnitude of the superimposed load was kept constant for over one hour at 7000 lbs. The testing machine was programmed to prevent load drop-off due to the relaxation of the material. Maximum bulging on the container occurred on side 1. This displacement was 3/8" from the no-load conditions.
5. Post-test inspection findings showed no damage to the container, with 1/16" distortion maximum, from the pre-stressed condition.

6. The container's performance was satisfactory when evaluated against the criteria established in paragraph 7, MIL-STD-1489A, Method 501.

TEST RESULTS (C)

1. Test Method 502, Racking Test
2. Conducted on: 12 May 1977
3. Method 502, Racking Test, was conducted in strict compliance with MIL-STD-1489A with no deviations.
4. Test measurements were as follows:
 - a. A 360 lb compressive force was necessary to lift the contractor's unrestricted sides just clear of the supporting surface.
 - b. The maximum change in length of a diagonal was 0.25" on side 1 in the direction away from the restricted side.
5. Post-test inspection findings show no damage to the container.
6. The container's performance was satisfactory when evaluated against the criteria established in paragraph 7, MIL-STD-1489A, Method 502.

TEST RESULTS (D)

1. Test Method 503, Pendulum Impact Test
2. Conducted on: 12 May 1977
3. Method 503, Pendulum Impact Test, was conducted in strict compliance with MIL-STD-1489A with no deviations.
4. No test measurements required.
5. Post-test inspection findings showed the following:
 - a. Three clip screw entry points showed slight cracks developing.
 - b. All seams opened slightly. This was mostly visible on the end/side seams.

6. The container's performance was satisfactory when evaluated against the criteria established in paragraph 7, MIL-STD-1489A, Method 503.

TEST RESULTS (E)


1. Test Method 504, Watertightness Test
2. Conducted on: 12 May 1977
3. Method 504, Watertightness Test, was conducted in strict compliance with MIL-STD-1489A with no deviations.
4. No test measurements required.
5. Post-test inspection findings revealed water on the interior sides and ends. The side/end seams showed a slight trace of water. The major area of water entrance was at the container interior top/side seals. There was a considerable amount of standing water covering approximately 60 percent of the floor.
6. The container's performance was unsatisfactory when evaluated against the criteria established in paragraph 7, MIL-STD-1489A, Method 504.

TEST RESULTS (F)

1. Test Method 505, Pendulum Puncture Test
2. Conducted on: 12 May 1977
3. Method 505, Pendulum Puncture Test, was conducted in strict compliance with MIL-STD-1489A with no deviations.
4. No test measurements required.
5. Post-test inspection findings found the impact surfaces pulled away from the lower horizontal cleats on each of the four impacts.
6. The container's performance was unsatisfactory when evaluated against the criteria established in paragraph 7, MIL-STD-1489A, Method 505.

SECTION 4 - VERIFICATION

The Air Force Packaging Evaluation Agency has no direct financial interest in either the design or manufacture of the container. The test equipment, test procedures, test conditions, and sequences of testing employed conformed to all applicable provisions of the document. The test report accurately depicts the test findings.



JACK E. THOMPSON

Director

Air Force Packaging
Evaluation Agency




FIGURE 9. SIDE VIEW - PAK-WELL CONTAINER
TOP CORNER AFTER DROP TEST SERIES




FIGURE 10. END VIEW - AFTER DROP TEST SERIES




FIGURE 11. END, RIGHT SIDE AFTER ROUGH HANDLING



FIGURE 12. END, LEFT SIDE AFTER ROUGH HANDLING




FIGURE 13. CLIMP SEPARATION AFTER ROUGH HANDLING




FIGURE 14. SIDE SEPARATION FROM PENDULUM PUNCTURE TEST




FIGURE 15. END SEPARATION AFTER PENDULUM IMPACT TEST



FIGURE 16. SIDE VIEW OF END SEPARATION

PHASE III

PROCEDURE

The following test report requirements are provided to comply with Appendix A of MIL-STD-1489A, "Performance Testing of Commercially Owned Household Goods Containers."

SECTION 1 - IDENTIFICATION INFORMATION

1. Test Report Date of Issuance -- 25 May 1977
2. Container Manufacturer -- Hughes Box & Container Co.
Baltimore MD
3. Testing Sponsor -- J. Burton, Federal Supply Service
4. Carrier Representative -- N/A
5. Test Laboratory -- Air Force Packaging Evaluation Agency
HQ AFALD/PTP
Wright-Patterson AFB OH 45433
6. Government Representatives -- Richard T. Gibbons
Frank R. Yeager
7. Container Built in Accordance With -- PPP-B-0058C (Navy)
Amendment 1. Deviations only as authorized in Government contract.

SECTION 2 - CONTAINER CONFIGURATION CHARACTERISTICS

1. Exterior Dimensions -- 96.5 x 42.5 x 84
2. Exterior Volume -- 199.4
3. Interior Dimensions -- 93.5 x 39.75 x 78.5
4. Interior Volume -- 168.8 cu ft
5. Ratio Interior to Exterior Volume -- 0.85:1
6. Tare Weight -- 415 lbs
7. Tare Density -- 2.08 pcf
8. Cube Utilization -- (8 x 8 x 20 VAN) - Actual - 4 containers with 582 cu ft unused volume.

SECTION 3

TEST RESULTS (A)

1. Test Method 500, Drop Test
2. Conducted on: 18 May 1977
3. Method 500, Drop Test, was conducted in strict compliance with MIL-STD-1489A, with no deviations.
4. No test measurements required.
5. Post inspection revealed the following:
 - a. At conclusion of edge drops there was only superficial damage evident.
 - b. At the conclusion of the corner drops only slight surface damage was noted.
6. The container's performance was satisfactory when evaluated against the criteria established in paragraph 7, Method 500 of MIL-STD-1489A.

TEST RESULTS (B)

1. Test Method 501, Stacking Test
2. Conducted on: 18 May 1977
3. Method 501, Stacking Test, was conducted in strict compliance with MIL-STD-1489A with no deviations. The test apparatus used to supply a constant test load was a Testing Machines Inc. (TMI), high capacity compression tester, model no. 17-24-2 with graphic and digital readout of load and deflection.
4. Test measurements. The magnitude of the superimposed load was kept constant for over one hour at 7100 lbs. The testing machine was programmed to prevent load drop-off due to the relaxation of the material. Maximum bulging on the container occurred on side #3. This displacement was 5/8" from the no-load conditions.
5. Post-test inspection findings showed no damage to the container.
6. The container's performance was satisfactory when evaluated against the criteria established in paragraph 7, MIL-STD-1489A, Method 501.

TEST RESULTS (C)

1. Test Method 502, Racking Test
2. Conducted on: 18 May 1977
3. Method 502, Racking Test, was conducted in strict compliance with MIL-STD-1489A with no deviations.
4. Test measurements were as follows:
 - a. A 360 lb compressive force was necessary to lift the container's unrestricted sides just clear of the supporting surface.
 - b. The maximum change in length of a diagonal was 0.50" on side #4 in the direction away from the restricted side.
5. Post-test inspection findings show no damage to the container.
6. The container's performance was satisfactory when evaluated against the criteria established in paragraph 7, MIL-STD-1489A, Method 502.

TEST RESULTS (D)

1. Test Method 503, Pendulum Impact Test
2. Conducted on: 18 May 1977
3. Method 503, Pendulum Impact Test, was conducted in strict compliance with MIL-STD-1489A with no deviations.
4. No test measurements required.
5. Post-test inspection findings showed the following:
 - a. Ten screw entry points showed cracks developing or spreading.
 - b. All seams opened slightly.
6. The container's performance was satisfactory when evaluated against the criteria established in paragraph 7, MIL-STD-1489A, Method 503.

TEST RESULTS (E)


1. Test Method 504, Watertightness Test
2. Conducted on: 18 May 1977
3. Method 504, Watertightness Test, was conducted in strict compliance with MIL-STD-1489A with no deviations.
4. No test measurements required.
5. Post-test inspection findings revealed a small amount of water on the interior sides and ends. The side/end seams showed a slight trace of water. The major area of water entrance was at the container interior base. There was a considerable amount of standing water covering approximately 45 percent of the floor.
6. The container's performance was unsatisfactory when evaluated against the criteria established in paragraph 7, MIL-STD-1489A, Method 504.

TEST RESULTS (F)

1. Test Method 505, Pendulum Puncture Test
2. Conducted on: 18 May 1977
3. Method 505, Pendulum Puncture Test, was conducted in strict compliance with MIL-STD-1489A with no deviations.
4. No test measurements required.
5. Post-test inspection findings found the impact surfaces pulled away from the lower horizontal cleats on one end and one side impact.
6. The container's performance was unsatisfactory when evaluated against the criteria established in paragraph 7, MIL-STD-1489A, Method 505.

SECTION 4 - VERIFICATION

The Air Force Packaging Evaluation Agency has no direct financial interest in either the design or manufacture of the container. The test equipment, test procedures, test conditions, and sequences of testing employed conformed to all applicable provisions of the document. The test report accurately depicts the test findings.



JACK E. THOMPSON

Director

Air Force Packaging
Evaluation Agency



FIGURE 17. TOP SIDE CORNER OF HUGHES CONTAINER



FIGURE 18. BOTTOM SIDE CORNER OF HUGHES CONTAINER




FIGURE 19. CRACKS DEVELOPING FROM BRACK SCREWS, LOWER CORNER




FIGURE 20. CRACKS DEVELOPING, UPPER CORNER




FIGURE 21. SEPARATION AND CRACKS FROM DROP TEST SERIES




FIGURE 22. SEPARATION AT MID-SIDE POINT



FIGURE 23. SEPARATION RESULTING FROM PENDULUM PUNCTURE




FIGURE 24. SIDE VIEW OF PUNCTURE TEST SEPARATION

PHASE IV

PROCEDURE

The following test report requirements are provided to comply with Appendix A of MIL-STD-1489A, "Performance Testing of Commercially Owned Household Goods Containers."

SECTION 1 - IDENTIFICATION INFORMATION

1. Test Report Date of Issuance -- 3 Jun 77
2. Container Manufacturer -- Rowley & Associates
1725 Hallam Drive
Lakeland, FL 33803
3. Testing Sponsor -- J. Burton, Federal Supply Service
4. Carrier Representative -- N/A
5. Test Laboratory -- Air Force Packaging Evaluation Agency
HQ AFALD/PTP
Wright-Patterson AFB OH 45433
6. Government Representatives -- Richard T. Gibbons
Frank R. Yeager
Daryl Edwards
7. Container Built in Accordance With -- PPP-B-00580 (Navy)
Amendment 1. Deviations only as authorized.

SECTION 2 - CONTAINER CONFIGURATION CHARACTERISTICS

1. Exterior Dimensions -- 87-1/8 X 47-1/8 X 87 inches
2. Exterior Volume -- 206.7 ft³
3. Interior Dimensions -- 84-1/8 X 44-3/8 X 81-1/2 inches
4. Interior Volume -- 176.1 ft³
5. Ratio Interior to Exterior Volume -- 0.85:1
6. Tare Weight -- 470
7. Tare Density -- 2.27 pcf

8. Cube Utilization -- (8 X 8 X 20 VAN) - Actual - 5 containers with 247 cu ft unused volume.

SECTION 3

TEST RESULTS (A)

1. Test Method 500, Drop Test
2. Conducted on: 20 May 1977
3. Method 500, Drop Test, was conducted in strict compliance with MIL-STD-1489A, with no deviations.
4. No test measurements required.
5. Post inspection revealed the following:
 - a. At conclusion of edge drops there was no visible detrimental damage.
 - b. At conclusion of corner drops there was no visible detrimental damage.
6. The container's performance was satisfactory when evaluated against the criteria established in paragraph 7, Method 500 of MIL-STD-1489A.

TEST RESULTS (B)

1. Test Method 501, Stacking Test
2. Conducted on: 24 May 1977
3. Method 501, Stacking Test, was conducted in strict compliance with MIL-STD-1489A with no deviations. The test apparatus used to provide a constant test load was a Testing Machines Inc. (TMI), high capacity compression tester, model no. 17-24-2 with graphic and digital read-out of load and deflection.
4. Test measurements. The magnitude of the superimposed load was kept constant for over one hour at 7130 lbs. The testing machine was programmed to prevent load drop-off due to the relaxation of the material. Maxi-

mum bulging on the container occurred on side #3. This displacement was 0.52" from the no-load conditions.

5. Post-test inspection findings showed no damage to the container. Permanent distortion was less than 0.1".
6. The container's performance was satisfactory when evaluated against the criteria established in paragraph 7, MIL-STD-1489A, Method 501.

TEST RESULTS (C)

1. Test Method 502, Racking Test
2. Conducted on: 25 May 1977
3. Method 502, Racking Test, was conducted in strict compliance with MIL-STD-1489A with no deviations.
4. Test measurements were as follows:
 - a. A 375 lb compressive force was necessary to lift the container's unrestricted sides just clear of the supporting surface.
 - b. The maximum change in length of a diagonal was 0.125" on side #2 in the direction away from the restricted side.
5. Post-test inspection findings show no damage to the container.
6. The container's performance was satisfactory when evaluated against the criteria established in paragraph 7, MIL-STD-1489A, Method 502.

TEST RESULTS (D)

1. Test Method 503, Pendulum Impact Test
2. Conducted on: 20 May 1977
3. Method 503, Pendulum Impact Test, was conducted in strict compliance with MIL-STD-1489A with no deviations.

4. No test measurements required.
5. Post-test inspection findings showed that there was no structural damage to the container.
6. The container's performance was satisfactory when evaluated against the criteria established in paragraph 7, MIL-STD-1489A, Method 503.

TEST RESULTS (E)

1. Test Method 504, Watertightness Test
2. Conducted on: 25 May 1977
3. Method 504, Watertightness Test, was conducted in strict compliance with MIL-STD-1489A with no deviations.
4. No test measurements required.
5. Post-test inspection findings revealed a small amount of water on the interior sides and ends. The side/end seams showed a slight trace of water. There was a considerable amount of standing water covering approximately 50 percent of the floor.
6. The container's performance was unsatisfactory when evaluated against the criteria established in paragraph 7, MIL-STD-1489A, Method 504.


TEST RESULTS (F)

1. Test Method 505, Pendulum Puncture Test
2. Conducted on: 27 May 1977
3. Method 505, Pendulum Puncture Test, was conducted in strict compliance with MIL-STD-1489A with no deviations.
4. No test measurements required.
5. Post-test inspection findings showed no critical damage.
6. The container's performance was satisfactory when evaluated against the criteria established in para-

graph 7, MIL-STD-1489A, Method 505.

SECTION 4 - VERIFICATION

The Air Force Packaging Evaluation Agency has no direct financial interest in either the design or manufacture of the container. The test equipment, test procedures, test conditions, and sequences of testing employed conformed to all applicable provisions of the document. The test report accurately depicts the test findings.



JACK E. THOMPSON

Director

Air Force Packaging
Evaluation Agency




FIGURE 25. OVERALL VIEW OF ROWLEY & ASSOCIATES CONTAINER



FIGURE 26. WATER INFILTRATION AREA, FRONT




FIGURE 27. WATER INFILTRATION, LEFT REAR




FIGURE 28. WATER INFILTRATION, RIGHT REAR

PHASE V

PROCEDURE

The following test report requirements are provided to comply with Appendix A of MIL-STD-1489A, "Performance Testing of Commercially Owned Household Goods Containers."

SECTION 1 - IDENTIFICATION INFORMATION

1. Test Report Date of Issuance -- 10 Jun 1977
2. Container Manufacturer -- WR-ALC/DSPC
3. Testing Sponsor -- J. Burton, Federal Supply Service
4. Carrier Representative -- N/A
5. Test Laboratory -- Air Force Packaging Evaluation Agency
HQ AFALD/PTP
Wright-Patterson AFB OH 45433
6. Government Representatives -- Richard T. Gibbons
Frank R. Yeager
Daryl Edwards
J. H. Schenck
7. Container Built in Accordance With -- PPP-B-00580 (Navy)
Amendment 1. Deviations only as authorized.

SECTION 2 - CONTAINER CONFIGURATION CHARACTERISTICS

1. Exterior Dimensions -- 87 X 47 X 87
2. Exterior Volume -- 205.9 cu ft
3. Interior Dimensions -- 84.75 X 44.75 X 81.5
4. Interior Volume -- 178.9 cu ft
5. Ratio Interior to Exterior Volume -- 0.87:1
6. Tare Weight -- 465
7. Tare Density -- 2.26 pcf
8. Cube Utilization -- (8 X 8 X 20 VAN) - Actual - 5 containers

with 250.7 cu ft unused volume

SECTION 3

TEST RESULTS (A)

1. Test Method 500, Drop Test
2. Conducted on: 7 Jun 1977
3. Method 500, Drop Test, was conducted in strict compliance with MIL-STD-1489A, with no deviations.
4. No test measurements required.
5. Post inspection revealed the following:
 - a. At conclusion of edge drops there was no apparent damage
 - b. At conclusion of corner drops - the bottom center clip hardware was pulled completely out on the side that had the column joiner in place of the hinge.
6. The container's performance was marginally satisfactory when evaluated against the criteria established in paragraph 7, Method 500 of MIL-STD-1489A.

TEST RESULTS (B)

1. Test Method 501, Stacking Test
2. Conducted on: 7 Jun 1977
3. Method 501, Stacking Test, was conducted in strict compliance with MIL-STD-1489A with no deviations. The test apparatus used to provide a constant test load was a Testing Machines Inc. (TMI), high capacity compression tester, model no. 17-24-2 with graphic and digital readout of load and deflection.
4. Test measurements. The magnitude of the superimposed load was kept constant for over one hour at 7130 lbs. The testing machine was programmed to prevent load drop-off due to the relaxation of the material. Maxi-

mum bulging on the container occurred on side #3. This displacement was 0.50" from the no-load conditions.

5. Post-test inspection findings showed no damage to the container. Permanent deformation was less than 1/16" maximum.
6. The container's performance was satisfactory when evaluated against the criteria established in paragraph 7, MIL-STD-1489A, Method 501.

TEST RESULTS (C)

1. Test Method 502, Racking Test
2. Conducted on: 7 Jun 1977
3. Method 502, Racking Test, was conducted in strict compliance with MIL-STD-1489A with no deviations.
4. Test measurements were as follows:
 - a. A 200 lb compressive force was necessary to lift the container's unrestricted sides just clear of the supporting surface.
 - b. The maximum change in length of a diagonal was 1/32" on side #4 in the direction away from the restricted side.
5. Post-test inspection findings show no damage to the container.
6. The container's performance was satisfactory when evaluated against the criteria established in paragraph 7, MIL-STD-1489A, Method 502.

TEST RESULTS (D)

1. Test Method 503, Pendulum Impact Test
2. Conducted on: 7 Jun 1977
3. Method 503, Pendulum Impact Test, was conducted in strict compliance with MIL-STD-1489A with no deviations.

4. No test measurements required.
5. Post-test inspection findings showed that there was no structural damage.
6. The container's performance was satisfactory when evaluated against the criteria established in paragraph 7, MIL-STD-1489A, Method 503.

TEST RESULTS (E)

1. Test Method 504, Watertightness Test
2. Conducted on: 8 Jun 77
3. Method 504, Watertightness Test, was conducted in strict compliance with MIL-STD-1489A with no deviations.
4. No test measurements required.
5. Post-test inspection findings revealed a large amount of water on the interior sides and ends. The side/end seams showed a slight trace of water. The major area of water entrance was at the container side seams. There was a considerable amount of standing water covering approximately 85 percent of the floor.
6. The container's performance was unsatisfactory when evaluated against the criteria established in paragraph 7, MIL-STD-1489A, Method 504.


TEST RESULTS (F)

1. Test Method 505, Pendulum Puncture Test
2. Conducted on: 8 Jun 77
3. Method 505, Pendulum Puncture Test, was conducted in strict compliance with MIL-STD-1489A with no deviations.
4. No test measurements required.
5. Post-test inspection findings showed no critical damage.
6. The container's performance was satisfactory when

evaluated against the criteria established in paragraph 7, MIL-STD-1489A, Method 505.

SECTION 4 - VERIFICATION

The Air Force Packaging Evaluation Agency has no direct financial interest in either the design or manufacture of the container. The test equipment, test procedures, test conditions, and sequences of testing employed conformed to all applicable provisions of the document. The test report accurately depicts the test findings.



JACK E. THOMPSON

Director

Air Force Packaging
Evaluation Agency




FIGURE 29. WR-ALC CONTAINER, DISASSEMBLED

DISCUSSION

All five containers tested had one common design flaw; one that was instrumental in the failure of each. The problem identified was that which showed all containers were unable to pass the watertightness test. The seal which provides the watertightness was ineffective, regardless of the type of sealing material used.

The first three containers tested, failed the pendulum puncture test. These containers, manufactured by Arbi Container Company, Inc., PAK-WELL, and the Hughes Box and Container Company all had the 1 x 4 cleating on the exterior of the container. The two containers that passed this phase of testing had the 1 x 4 cleating on the box interior. The positioning of the cleats was then, seen to be the determining factor as to whether or not the container passed the test. Whether or not the staples used in construction of the end and side panels were clinched appeared to have no effect on the container performance during the puncture test.

A sixth container, manufactured by Blakely, arrived at the AFPEA in such poor condition that testing was not conducted. The maximum amount of caulking allowed would not have prevented water infiltration when subjected to the watertightness test outlined in MIL-STD-1489A.

The container manufactured by Rowley & Associates seemed to have the best overall performance, and with improved seal design, the container should have no problems passing all tests in MIL-STD-1489A.

The container manufactured by WR-ALC personnel was designed with a hinged side section for better knocked-down stacking and transportation. By using this hinge, all container panels become approximately the same size. With a proper seal design between the hinged sections, as well as at the standard joints, this container could prove to be the most effective design.

Testing on all containers was terminated after the pendulum puncture test to provide uniform evaluation. At this point, all containers had failed.

RECOMMENDATIONS

The Air Force Packaging Evaluation Agency makes the following recommendations based on recently completed testing and evaluation of six household goods containers, one each from six different manufacturers:

1. MIL-STD-1489A should be evaluated and improved so as to provide

a more representative, accurate, and fully reproducible test plan for container evaluation. AFPEA will, of course, have some initial input for this effort.

2. Cleats (1 x 4's) should be used on the inside rather than outside of the container to prevent staple pull-out from the plywood/cleat construction.

3. A redesign of the seal area is imperative. The water infiltration problem, common to all containers tested, supports this recommendation. If the present type of seal design is retained, then an effort should be made to alter or amend the MIL-STD-1489A water test since the present containers fabricated in accordance with the specification will not pass this test.

DISTRIBUTION LIST

HQ USAF/LGTN Washington DC 20330	2
DDC-TC (Accessions Division) Alexandria VA 22314	2
Tobyhanna Army Depot/DRXTO-TP-S Tobyhanna PA 18466	2
HQ AFSC/LGT Andrews AFB DC 20334	1
OO-ALC/DSTC Hill AFB UT 84406	6
OC-ALC/DSP Tinker AFB OK 73145	2
SA-ALC/DSP Kelly AFB TX 78241	2
SM-ALC/DSP McClellan AFB CA 95652	2
WR-ALC/DSP Robins AFB GA 31098	2
DCASR/DCRS-PS 1136 Washington Ave St Louis MO 63101	3
Aviation Supply Office ATTN: TEP-A Philadelphia PA 19111	1
ADTC/SDMT Eglin AFB FL 32542	1
JMPTC Aberdeen Proving Ground MD 21005	2
Commander US Army Natick R&D Ctr/DRXNM-EP Natick MA 01760	1

DESC/LQP 1507 Wilmington Pike Dayton OH 45444	1
AFALD/PT	1
AFLC/LOT	1
AFALD/PTP LIBRARY	10
ASD/AEGP WPAFB OH 45433	1
NWC-EARLE Colts Neck NJ 07722	1
2750 LS/DMTTH WPAFB OH 45433	1
HQ MTMC/M7-PPQ Washington DC 20301	5
Director Military Traffic Management & Terminal Service Transportation Engineering Agency ATTN: MTT-CD PO Box 6276 Newport News VA 23606	5
Naval Supply Systems Command Packaging and Storage (Sup 0521C) Washington DC 20376	2
GSA/FMFP Washington DC	5
DCASR, Atlanta ATTN: Mr. E. Lloyd 3100 Maple Drive Atlanta GA 30305	1
DCASR, Boston 666 Summer Street Boston MA 02101	1

DCASR, Chicago O'Hare Intl Airport PO Box 66475 Chicago IL 60666	1
DCASR, Cleveland 1240 East Ninth Street Cleveland OH 44199	1
DCASR, Dallas 500 South Ervay Street Dallas TX 75201	1
DCASR, Detroit 1580 East Grand Blvd Detroit MI 48211	1
DCASR, Los Angeles 11099 S. La Cienega Blvd Los Angeles CA 90045	1
DCASR, New York 60 Hudson Street New York NY 10013	1
Dcasr, Philadelphia 2800 South 20th Street PO Box 7478 Philadelphia PA 19101	1
DCASR, San Francisco 866 Malcolm Road Burlingame CA 94010	1
Director Defense Supply Agency ATTN: DCAS-HT Cameron Station Alexandria VA 22314	1

14 PTPD-77-22

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER PTPD REPORT NO. 77-22	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) TESTING AND ANALYSIS OF HOUSEHOLD CONTAINERS	5. TYPE OF REPORT & PERIOD COVERED Test Data Apr - June 77	
7. AUTHOR(s) Richard T. Gibbons	6. PERFORMING ORG. REPORT NUMBER AFPEA Project No. 77-P7-23	
9. PERFORMING ORGANIZATION NAME AND ADDRESS AFALD/PTP Air Force Packaging Evaluation Agency Wright-Patterson AFB OH 45433	8. CONTRACT OR GRANT NUMBER(s)	
11. CONTROLLING OFFICE NAME AND ADDRESS AFALD/PTPD Air Force Packaging Evaluation Agency Wright-Patterson AFB OH 45433	10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS	
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)	12. REPORT DATE 11 Jul 77	
	13. NUMBER OF PAGES 62 (2) 51p	
	15. SECURITY CLASS. (of this report) Unclassified	
16. DISTRIBUTION STATEMENT (of this Report) DISTRIBUTION LIMITED to U. S. Government agencies only; report involves evaluation of commercial products . Other requests for this document must be referred to AFALD/PTP, Wright-Patterson AFB OH 45433.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Container Rough Handling Household Goods Transportation Testing Crates		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) As part of the Air Force Packaging Evaluation Agency (AFPEA) mission, test and evaluation services are available to all agencies in the DOD. These services are used to evaluate a single container design or to compare and contrast various designs and products from a variety of sources. Through this engineering effort, AFPEA is able to help make sure the best and most economical containers are used in the transportation system. Recently, the Design Division of AFALD/PTP conducted testing (Cont'd)		

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

63 SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

403519

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

→ and evaluation of six household goods containers. While none of the containers passed the testing criteria established, there was ample opportunity to observe the effect of variations in construction. It is very probable that with more emphasis on the container seal design, one or more of the tested containers can successfully pass all tests required. ↑

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)